Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

March 01, 2019

Rob King
Hampton Bays Water District
P.O. Box 1013
Hampton Bays, NY 11946

RE: Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

Dear Rob King:
Enclosed are the analytical results for sample(s) received by the laboratory on February 28, 2019. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Stu Murrell
stu.murrell@pacelabs.com
(631)694-3040
Project Manager

Enclosures

cc: Warren Booth, Hampton Bays Water District
John Collins, H2M Group
Stella Michaels, Hampton Bays Water District
Paul Ponturo, H2M Group

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

CERTIFICATIONS

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

Long Island Certification IDs

575 Broad Hollow Rd, Melville, NY 11747
New York Certification #: 10478 Primary Accrediting Body
New Jersey Certification #: NY158
Pennsylvania Certification #: 68-00350
Connecticut Certification #: PH-0435
Maryland Certification #: 208
Rhode Island Certification #: LAO00340
Massachusetts Certification #: M-NY026
New Hampshire Certification #: 2987

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

SAMPLE SUMMARY

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

Lab ID	Sample ID	Matrix	Date Collected	Date Received
7080921001	**7 WELLS LANE**	Drinking Water	02/28/19 08:17	02/28/19 10:25

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

SAMPLE ANALYTE COUNT

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

Lab ID	Sample ID	Method	Analysts	Analytes Reported
7080921001	**7 WELLS LANE**	EPA 200.7	CAM	2
		SM22 9223B Colilert	AL1	2

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

ANALYTICAL RESULTS

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

Sample: 7 WELLS LANE **Lab ID: 7080921001** Collected: 02/28/19 08:17 Received: 02/28/19 10:25 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	Reg. Limit	DF	Prepared	Analyzed	CAS No.	Qual
Field Chlorine and pH	Analytical Method:								
Field Residual Chlorine	**0.28**	mg/L			1		02/28/19 08:17		N3
200.7 MET ICP, Drinking Water	Analytical Method: EPA 200.7								
Iron	**0.040**	mg/L	0.020		1		03/01/19 13:22	7439-89-6	
Manganese	**<0.010**	mg/L	0.010		1		03/01/19 13:22	7439-96-5	
MBIO Total Coliform DW	Analytical Method: SM22 9223B Colilert Preparation Method: SM22 9223B Colilert								
Total Coliforms	**Absent**				1	02/28/19 18:35	03/01/19 12:35		
E.coli	**Absent**				1	02/28/19 18:35	03/01/19 12:35		

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALITY CONTROL DATA

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

QC Batch: 103745
QC Batch Method: EPA 200.7
Analysis Method: EPA 200.7
Analysis Description: 200.7 MET No Prep Drinking Water
Associated Lab Samples: 7080921001

METHOD BLANK: 479835
Matrix: Drinking Water
Associated Lab Samples: 7080921001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Iron	mg/L	<0.020	0.020	03/01/19 13:15	
Manganese	mg/L	<0.010	0.010	03/01/19 13:15	

LABORATORY CONTROL SAMPLE: 479836

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	2	2.0	100	85-115	
Manganese	mg/L	0.25	0.25	98	85-115	

MATRIX SPIKE SAMPLE: 479839

Parameter	Units	7080863004 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	<20.0 ug/L	2	2.0	100	70-130	
Manganese	mg/L	<10.0 ug/L	0.25	0.24	98	70-130	

MATRIX SPIKE SAMPLE: 479841

Parameter	Units	7080921001 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Iron	mg/L	0.040	2	2.1	103	70-130	
Manganese	mg/L	<0.010	0.25	0.26	101	70-130	

SAMPLE DUPLICATE: 479838

Parameter	Units	7080863004 Result	Dup Result	RPD	Max RPD	Qualifiers
Iron	mg/L	<20.0 ug/L	<0.020		20	
Manganese	mg/L	<10.0 ug/L	<0.010		20	

SAMPLE DUPLICATE: 479840

Parameter	Units	7080921001 Result	Dup Result	RPD	Max RPD	Qualifiers
Iron	mg/L	0.040	0.038	7	20	
Manganese	mg/L	<0.010	<0.010		20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALITY CONTROL DATA

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

QC Batch: 103672 Analysis Method: SM22 9223B Colilert
QC Batch Method: SM22 9223B Colilert Analysis Description: TotColDW MBIO Total Coliform
Associated Lab Samples: 7080921001

METHOD BLANK: 479613 Matrix: Drinking Water
Associated Lab Samples: 7080921001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
E.coli		Absent		03/01/19 12:35	
Total Coliforms		Absent		03/01/19 12:35	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALIFIERS

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

N3 Accreditation is not offered by the relevant laboratory accrediting body for this parameter.

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: BACT/FE/MN 2/28
Pace Project No.: 7080921

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
7080921001	**7 WELLS LANE**		103738		
7080921001	**7 WELLS LANE**	EPA 200.7	103745		
7080921001	**7 WELLS LANE**	SM22 9223B Colilert	103672	SM22 9223B Colilert	103794

WO#: 7080921

7080921

Sample Request Form
PUBLIC WATER SUPPLIER

Date: 2/28/19

Collected By: J. Ruppert

Accepted By: [signature] 2/28/19 10:25

Cooler Temp: 4.5 °C

❑ WELL OFF LINE _____

❑ WELL RUN TO SYSTEM _____

❑ YES ❑ NO VOC'S PRESERVED WITH HCl

Client Info:

Name or Code: HAMPTON BAYS WATER DISTRICT

Address: P.O. BOX 1013 HAMPTON BAYS, NEW YORK 11946 (631) 728-0179

Phone #: _____

Attn: _____

Proj. # or (Name): _____

Bill To: _____

Copies To: _____

Sample Types	Purpose	Origin	Treatment Types
PW - Potable Water	RO - Routine	D - Distribution	AST - Air Stripper
GW - Groundwater	RE - Resample	RW - Raw Well	GAC - Granular Activated Charcoal
SW - Surface Water	S - Special	TW - Treated Well	N - Nitrate Removal Plant
WW - Waste Water		T - Tank	FE - Iron Removal Plant
AQ - Aqueous		MW - Monitoring Well	O - Other
S - Soil		I - Influent	
		E - Effluent	

Sample Info:

Date/Time Collected:	Sample Type	Location	Origin	Treatment Type	Purpose	Field Readings Cl_2	Field Readings pH/Temp	Analysis	Lab No.
2/28/19 8:17am	PW	7 Wells Lane	D	-	S	.28	7.38	PFC's, Bact., Iron & Magnese	001

Remarks: *RUSH*

Sample Condition Upon Receipt

Pace Analytical® Long Island Laboratory

Client Name: HBW

Proje WO#:7080921

PM: SWM Due Date: 03/30/19

CLIENT: HBW

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☑ Client ☐ Commercial ☐ Pace ☐ Other

Tracking #:

Custody Seal on Cooler/Box Present: ☐ Yes ☑ No **Seals intact:** ☐ Yes ☑ No **Temperature Blank Present:** ☐ Yes ☐ No

Packing Material: ☐ Bubble Wrap ☐ Bubble Bags ☐ Ziploc ☑ None ☐ Other **Type of Ice:** Wet Blue None

Thermometer Used: TH091 **Correction Factor:** 0.0 ☐ Samples on ice, cooling process has begun

Cooler Temperature (°C): 4.5 **Cooler Temperature Corrected (°C):** 4.5 **Date/Time 5035A kits placed in freezer**

Temp should be above freezing to 6.0°C

USDA Regulated Soil (☐ N/A, water sample) **Date and Initials of person examining contents:** CH 2/28/19

Did samples originate in a quarantine zone within the United States: AL, AR, CA, FL, GA, ID, LA, MS, NC, NM, NY, OK, OR, SC, TN, TX, or VA (check map)? ☐ YES ☐ NO

Did samples orignate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

If Yes to either question, fill out a Regulated Soil Checklist (F-LI-C-010) and include with SCUR/COC paperwork.

				COMMENTS:
Chain of Custody Present:	☑Yes	☐No		1.
Chain of Custody Filled Out:	☑Yes	☐No		2.
Chain of Custody Relinquished:	☑Yes	☐No		3.
Sampler Name & Signature on COC:	☑Yes	☐No	☐N/A	4.
Samples Arrived within Hold Time:	☑Yes	☐No		5.
Short Hold Time Analysis (<72hr):	☑Yes	☐No		6.
Rush Turn Around Time Requested:	☑Yes	☐No		7.
Sufficient Volume: (Triple volume provided for MS/MSD	☑Yes	☐No		8.
Correct Containers Used:	☑Yes	☐No		9.
-Pace Containers Used:	☑Yes	☐No		
Containers Intact:	☑Yes	☐No		10.
Filtered volume received for Dissolved tests	☐Yes	☐No	☑N/A	11. Note if sediment is visible in the dissolved container.
Sample Labels match COC:	☑Yes	☐No		12.
-Includes date/time/ID/Analysis Matrix SL WT OIL				
All containers needing preservation have been checked	☐Yes	☐No	☑N/A	13. ☐ HNO_3 ☐ H_2SO_4 ☐ NaOH ☐ HCl
pH paper Lot #				
All containers needing preservation are found to be in compliance with EPA recommendation? (HNO_3, H_2SO_4, HCl, NaOH>9 Sulfide, NAOH>12 Cyanide) Exceptions: VOA, Coliform, TOC/DOC, Oil and Grease, DRO/8015 (water). Per Method, VOA pH is checked after analysis	☐Yes	☐No	☑N/A	Sample #
				Initial when completed: / Lot # of added preservative: / Date/Time preservative added:
Samples checked for dechlorination:	☐Yes	☐No	☑N/A	14.
KI starch test strips Lot #				
Residual chlorine strips Lot #				Positive for Res. Chlorine? Y N
Headspace in VOA Vials (>6mm):	☐Yes	☐No	☑N/A	15.
Trip Blank Present:	☐Yes	☑No	☐N/A	16.
Trip Blank Custody Seals Present	☐Yes	☐No	☐N/A	
Pace Trip Blank Lot # (if applicable):				

Client Notification/ Resolution: Field Data Required? Y / N

Person Contacted: Date/Time:

Comments/ Resolution:

* PM (Project Manager) review is documented electronically in LIMS.