Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

April 12, 2019

Rob King
Hampton Bays Water District
P.O. Box 1013
Hampton Bays, NY 11946

RE: Project: NO2/NO3 4/10
Pace Project No.: 7085312

Dear Rob King:
Enclosed are the analytical results for sample(s) received by the laboratory on April 10, 2019. The results relate only to the samples included in this report. Results reported herein conform to the most current, applicable TNI/NELAC standards and the laboratory's Quality Assurance Manual, where applicable, unless otherwise noted in the body of the report.

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Stu Murrell
stu.murrell@pacelabs.com
(631)694-3040
Project Manager

Enclosures

cc: Warren Booth, Hampton Bays Water District
John Collins, H2M Group
Stella Michaels, Hampton Bays Water District
Paul Ponturo, H2M Group

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

CERTIFICATIONS

Project: NO2/NO3 4/10
Pace Project No.: 7085312

Long Island Certification IDs

575 Broad Hollow Rd, Melville, NY 11747
New York Certification #: 10478 Primary Accrediting Body
New Jersey Certification #: NY158
Pennsylvania Certification #: 68-00350
Connecticut Certification #: PH-0435
Maryland Certification #: 208
Rhode Island Certification #: LAO00340
Massachusetts Certification #: M-NY026
New Hampshire Certification #: 2987

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

SAMPLE SUMMARY

Project: NO2/NO3 4/10
Pace Project No.: 7085312

Lab ID	Sample ID	Matrix	Date Collected	Date Received
7085312001	**HB12**	Drinking Water	04/10/19 08:00	04/10/19 11:20
7085312002	**HB5A**	Drinking Water	04/10/19 10:15	04/10/19 11:20

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

SAMPLE ANALYTE COUNT

Project: NO2/NO3 4/10
Pace Project No.: 7085312

Lab ID	Sample ID	Method	Analysts	Analytes Reported
7085312001	**HB12**	EPA 353.2	SDO	2
		EPA 353.2	SDO	1
7085312002	**HB5A**	EPA 353.2	SDO	2
		EPA 353.2	SDO	1

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

ANALYTICAL RESULTS

Project: NO2/NO3 4/10
Pace Project No.: 7085312

Sample: HB12 **Lab ID: 7085312001** Collected: 04/10/19 08:00 Received: 04/10/19 11:20 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	Reg. Limit	DF	Prepared	Analyzed	CAS No.	Qual
353.2 Nitrogen, NO2/NO3 unpres	Analytical Method: EPA 353.2								
Nitrate as N	**2.1**	mg/L	0.50		10		04/10/19 22:50	14797-55-8	
Nitrate-Nitrite (as N)	**2.1**	mg/L	0.50		10		04/10/19 22:50	7727-37-9	
353.2 Nitrogen, NO2	Analytical Method: EPA 353.2								
Nitrite as N	**<0.050**	mg/L	0.050		1		04/10/19 19:52	14797-65-0	

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

ANALYTICAL RESULTS

Project: NO2/NO3 4/10
Pace Project No.: 7085312

Sample: HB5A **Lab ID: 7085312002** Collected: 04/10/19 10:15 Received: 04/10/19 11:20 Matrix: Drinking Water

Parameters	Results	Units	Report Limit	Reg. Limit	DF	Prepared	Analyzed	CAS No.	Qual
353.2 Nitrogen, NO2/NO3 unpres	Analytical Method: EPA 353.2								
Nitrate as N	**2.7**	mg/L	0.50		10		04/10/19 22:51	14797-55-8	
Nitrate-Nitrite (as N)	**2.7**	mg/L	0.50		10		04/10/19 22:51	7727-37-9	
353.2 Nitrogen, NO2	Analytical Method: EPA 353.2								
Nitrite as N	**<0.050**	mg/L	0.050		1		04/10/19 19:53	14797-65-0	

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALITY CONTROL DATA

Project: NO2/NO3 4/10
Pace Project No.: 7085312

QC Batch: 108916
QC Batch Method: EPA 353.2
Analysis Method: EPA 353.2
Analysis Description: 353.2 Nitrite, Unpres.
Associated Lab Samples: 7085312001, 7085312002

METHOD BLANK: 505124 Matrix: Water
Associated Lab Samples: 7085312001, 7085312002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrite as N	mg/L	<0.050	0.050	04/10/19 19:35	

LABORATORY CONTROL SAMPLE: 505125

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrite as N	mg/L	1	1.1	110	90-110	

MATRIX SPIKE SAMPLE: 505126

Parameter	Units	7085283001 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Nitrite as N	mg/L	<0.050	0.5	0.55	107	90-110	

MATRIX SPIKE SAMPLE: 505128

Parameter	Units	7085304002 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Nitrite as N	mg/L	<0.050	0.5	0.52	104	90-110	

SAMPLE DUPLICATE: 505127

Parameter	Units	7085283001 Result	Dup Result	RPD	Max RPD	Qualifiers
Nitrite as N	mg/L	<0.050	<0.050		20	

SAMPLE DUPLICATE: 505129

Parameter	Units	7085304002 Result	Dup Result	RPD	Max RPD	Qualifiers
Nitrite as N	mg/L	<0.050	<0.050		20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALITY CONTROL DATA

Project: NO2/NO3 4/10
Pace Project No.: 7085312

QC Batch: 108926
QC Batch Method: EPA 353.2
Analysis Method: EPA 353.2
Analysis Description: 353.2 Nitrate, Unpres.
Associated Lab Samples: 7085312001, 7085312002

METHOD BLANK: 505314 Matrix: Water
Associated Lab Samples: 7085312001, 7085312002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrate-Nitrite (as N)	mg/L	<0.050	0.050	04/11/19 01:35	

LABORATORY CONTROL SAMPLE: 505315

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrate-Nitrite (as N)	mg/L	1	1.0	103	90-110	

MATRIX SPIKE SAMPLE: 505316

Parameter	Units	7085312002 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Nitrate-Nitrite (as N)	mg/L	2.7	5	7.4	95	90-110	

MATRIX SPIKE SAMPLE: 505318

Parameter	Units	7085347001 Result	Spike Conc.	MS Result	MS % Rec	% Rec Limits	Qualifiers
Nitrate-Nitrite (as N)	mg/L	2.8	5	7.3	90	90-110	

SAMPLE DUPLICATE: 505317

Parameter	Units	7085312002 Result	Dup Result	RPD	Max RPD	Qualifiers
Nitrate-Nitrite (as N)	mg/L	2.7	2.3	17	20	

SAMPLE DUPLICATE: 505319

Parameter	Units	7085347001 Result	Dup Result	RPD	Max RPD	Qualifiers
Nitrate-Nitrite (as N)	mg/L	2.8	3.4	17	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALIFIERS

Project: NO2/NO3 4/10
Pace Project No.: 7085312

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

J - Estimated concentration above the adjusted method detection limit and below the adjusted reporting limit.

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

Pace Analytical Services, LLC
575 Broad Hollow Road
Melville, NY 11747
(631)694-3040

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: NO2/NO3 4/10
Pace Project No.: 7085312

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
7085312001	**HB12**	EPA 353.2	108926		
7085312002	**HB5A**	EPA 353.2	108926		
7085312001	**HB12**	EPA 353.2	108916		
7085312002	**HB5A**	EPA 353.2	108916		

WO#:7085312

7085312

Sample Request Form
PUBLIC WATER SUPPLIER

Date: 4-10-19 4/10/19

Collected By: G. VALENTINO 1350

Accepted By:

Cooler Temp: 3.2°C

❑ WELL OFF LINE _____

❑ WELL RUN TO SYSTEM _____

❑ YES ❑ NO VOC'S PRESERVED WITH HCl

Back 1700

Client Info:

Name or Code: HAMPTON BAYS WATER DISTRICT

Address: P.O. BOX 1013 HAMPTON BAYS, NEW YORK 11946 (631) 728-0179

Phone #:

Attn:

Proj. # or (Name):

Bill To:

Copies To:

Sample Types	Purpose	Origin	Treatment Types
PW - Potable Water	RO - Routine	D - Distribution	AST - Air Stripper
GW - Groundwater	RE - Resample	RW - Raw Well	GAC - Granular Activated Charcoal
SW - Surface Water	S - Special	TW - Treated Well	N - Nitrate Removal Plant
WW - Waste Water		T - Tank	FE - Iron Removal Plant
AQ - Aqueous		MW - Monitoring Well	O - Other
S - Soil		I - Influent	
		E - Effluent	

Sample Info:

Date/Time Collected:	Sample Type	Location	Origin	Treatment Type	Purpose	Field Readings Cl_2	Field Readings pH/Temp	Analysis	Lab No.
4-10-19	PW	#12 700	D	-	RO	.29	7.58	BACT w/CL, N/N	001
4-10-19	PW	#13 815	D	-	RO	.48	7.38	BACT w/CL	
4-10-19	PW	#28 830	D	-	RO	.65	7.36	BACT w/CL	
4-10-19	PW	#29 930	D	-	RO	.56	7.44	BACT w/CL	
4-10-19	PW	#16 845	D	-	RO	.59	7.41	BACT w/CL	
4-10-19	PW	#31 900	D	-	RO	.69	7.38	BACT w/CL	
4-10-19	PW	#25 915	D	-	RO	.53	7.44	BACT w/CL	
4-10-19	PW	#33 945	D	-	RO	.55	7.59	BACT w/CL	
4-10-19	PW	#21 1000	D	-	RO	.52	7.43	BACT w/CL	
4-10-19	PW	#5A 1015	D	-	RO	.24	7.64	BACT w/CL, N/N	002
4-10-19	PW	RATTLER 830 WW	D	-	S			BACT, IRON, MANG.	003

Remarks:

Pace Analytical
Long Island Laboratory

Sample Condition Upon Receipt

WO#: 7085312
PM: SWM Due Date: 04/16/19
CLIENT: HBW

Client Name: HBW Proj

Courier: ☐ Fed Ex ☐ UPS ☐ USPS ☐ Client ☐ Commercial ☐ Pace ☐ Other

Tracking #:

Custody Seal on Cooler/Box Present: ☐ Yes ☐ No Seals intact: ☐ Yes ☐ No

Temperature Blank Present: ☐ Yes ☐ No

Packing Material: ☐ Bubble Wrap ☐ Bubble Bags ☐ Ziploc ☐ None ☐ Other

Type of Ice: Wet Blue None

Thermometer Used: TH091 Correction Factor: 0.0

☐ Samples on ice, cooling process has begun

Cooler Temperature (°C): 3.2 Cooler Temperature Corrected (°C): 3.2

Date/Time 5035A kits placed in freezer

Temp should be above freezing to 6.0°C

USDA Regulated Soil (☐ N/A, water sample) Date and Initials of person examining contents: cd 4/10/19

Did samples originate in a quarantine zone within the United States: AL, AR, CA, FL, GA, ID, LA, MS, NC, NM, NY, OK, OR, SC, TN, TX, or VA (check map)? ☐ YES ☐ NO

Did samples orignate from a foreign source (internationally, including Hawaii and Puerto Rico)? ☐ Yes ☒ No

If Yes to either question, fill out a Regulated Soil Checklist (F-LI-C-010) and include with SCUR/COC paperwork.

				COMMENTS:
Chain of Custody Present:	☑Yes	☐No		1.
Chain of Custody Filled Out:	☑Yes	☐No		2.
Chain of Custody Relinquished:	☑Yes	☐No		3.
Sampler Name & Signature on COC:	☑Yes	☐No	☐N/A	4.
Samples Arrived within Hold Time:	☑Yes	☐No		5.
Short Hold Time Analysis (<72hr):	☐Yes	☑No		6.
Rush Turn Around Time Requested:	☐Yes	☑No		7.
Sufficient Volume: (Triple volume provided for MS/MSD)	☑Yes	☐No		8.
Correct Containers Used:	☑Yes	☐No		9.
-Pace Containers Used:	☑Yes	☐No		
Containers Intact:	☑Yes	☐No		10.
Filtered volume received for Dissolved tests	☐Yes	☐No	☑N/A	11. Note if sediment is visible in the dissolved container.
Sample Labels match COC: -Includes date/time/ID/Analysis Matrix SL WT OIL	☑Yes	☐No		12.
All containers needing preservation have been checked pH paper Lot # HC857466	☑Yes	☐No	☑N/A	13. ☐ HNO_3 ☐ H_2SO_4 ☐ NaOH ☐ HCl Sample #
All containers needing preservation are found to be in compliance with EPA recommendation? (HNO_3, H_2SO_4, HCl, NaOH>9 Sulfide, NAOH>12 Cyanide) Exceptions: VOA, Coliform, TOC/DOC, Oil and Grease, DRO/8015 (water). Per Method, VOA pH is checked after analysis	☑Yes	☐No	☑N/A	Initial when completed: / Lot # of added preservative: / Date/Time preservative added:
Samples checked for dechlorination: KI starch test strips Lot # Residual chlorine strips Lot #	☐Yes	☐No	☐N/A	14. Positive for Res. Chlorine? Y N
Headspace in VOA Vials (>6mm):	☐Yes	☐No	☐N/A	15.
Trip Blank Present:	☐Yes	☐No	☐N/A	16.
Trip Blank Custody Seals Present	☐Yes	☐No	☐N/A	
Pace Trip Blank Lot # (if applicable):				

Client Notification/ Resolution: Field Data Required? Y / N

Person Contacted: Date/Time:

Comments/ Resolution:

* PM (Project Manager) review is documented electronically in LIMS.